



BIHAR POLICE BUILDINGS CONSTRUCTIONS CORPORATION
(A Govt. of Bihar Undertaking)
Kautilya Nagar, Patna- 14

www.bpbcc.co.in, Phone No.0612-2223727, Fax No.-0612-2224529


Quotation Invitation Notice no.- 09/2017-18

Open quotations are invited for Bihar Institute of Correctional Administration (BICA), Hajipur in the District of Vaishali in sealed envelope from reputed manufacturers or, their authorised dealers meeting the specification given in annexure-I for supply & Installation of **REQUIRED POLYESTER FABRIC WITH PVDF QUOTED, H.T. POLYESTER YARN 1100 Dte MINIMUM WEIGHT SHOULD BE 900g/ Sqm.**

Details of required materials along with their specifications make are given in annexure-I and may be seen on our website www.bpbcc.co.in.

The sealed envelope with title of the quotation should be received in the office of undersigned latest by **3 p.m. on 04-10-2017**.

The undersigned reserves all rights to accept or reject one or, all quotations without assigning any reason.


18/9/2017
Chief Engineer

Annexure-I

BIHAR POLICE BUILDINGS CONSTRUCTIONS CORPORATION

Quotation Invitation Notice No. - 09/2017-18

REQUIRED POLYESTER FABRIC WITH PVDF QUOTED, H.T. POLYESTER YARN 1100 Dte MINIMUM WEIGHT SHOULD BE 900 g/ Sqm

| Sl. NO. | Materials description | Unit | Quantity | Rate | Amount in Rs. | Remarks |
|--|---|------|----------|------|---------------|---------|
| 1 | <p>Supplying, installation, fabricating, assembling and erection of polyester fabric with PVDF coated, HT polyester yarns 1100 Dte minimum weight should be 900g/sqm (EN ISO 2286-2), Minimum Tensile strength should be 4300N/5cm in warp and 4200 N/5cm in weft directions (EN ISO 1421), minimum Tear strength should be 500N in warp and 500N in weft (DIN 53.363). Flame retardancy Bs2d0- Quality in conformity with ISO 9001. Along with steel frames with steel frames with all fittings and fixtures such as Galvanized MS Membrane /End plate,</p> <p>shackles, Rigging Screws, Turnbuckles, swedge, fork, keder rods and galvanized MS strands/ cable with stainless steel end terminals complete as per drawing / Details and as per technical specifications and as per the instructions of Engineer-in-charge. (Rate including cost of fabric, shop drawings, patterning , from finding , cutting, fabrication , high frequency welding of fabric, Transport to the site assembling and installation with GI cables, hardware, EPDM gasket and required accessories, necessary scaffolding etc. required for all operations in all respect as per direction of Engineer-in-charge). (Measurement as per actual area of fabric on plan for payment) (The approved make is Serge Ferrari/Mehler or equivalent).</p> | Sqm | 653.100 | | | |
| | Total amounts in figures | | | | | |
| Total amounts in words - Rupees | | | | | | |